HTB ELECTRICAL & AIR CONDITIONING PTY LTD

ABN 54 168 092 466 | Licence 376869C

QUOTE

0403 116 368 | htbelectricalandaircon@outllook.com

BILL TO	CLIENT / SITE	QUOTE DETAILS
Rebecca Knox 5/295 Ernest St, Neutral Bay	Rebecca Knox	**Quote No.** HTB59 **Date** 4th November 2026

DESCRIPTION	QTY	PRICE
Supply & install new double WGPO in bathroom • Tap off existing double power point on kitchen splashback • Run new cable through wall cavity behind tiles to bathroom wall – **cable fully concealed behind the wall, no exposed cabling** • Cut tile & install new double WGPO next to mirror, 400 mm above vanity (cable entering from left side) • Test, RCD check & Certificate of Compliance *Proposed cable route shown in attached photos (page 2).*	1	$500.00

SUBTOTAL	$500.00
GST	$50.00
TOTAL	**$550.00**

TERMS & CONDITIONS

Air Conditioning:

- Deposit: Upon acceptance of this quote, a 60% deposit is required to allow us to order the air conditioning unit and the materials required for the job
- Final payment: The remaining 40% balance is payable upon completion of the work.
- Warranty: We provide a 5-year manufacturer's warranty on the air conditioning unit, together with a 1-year warranty on our installation workmanship, subject to the applicable warranty terms and conditions.
- Quote Validity: This quote is valid for 10 working days from the date of issue. After this period, pricing and availability may be subject to change.

Electrical:

- Payment is payable upon completion of the work
- This quote will be expired in 10 working days

Method of payment:

Bank Transfer (EFT) **Name**: HTB ELECTRICAL & AIR CONDITIONDING P/L
BSB: 082 343
Account Number: 84 378 4720

Or pay ID to 0403 116 368

We sincerely appreciate the opportunity and look forward to doing business with you.

HTB ELECTRICAL & AIR CONDITIONING PTY LTD
ABN 54 168 092 466 | Licence 376869C

QUOTE

0403 116 368 | htbelectricalandaircon@outllook.com

PROPOSED CABLE ROUTE – Quote No. HTB59



Photo 1 – Kitchen: Tap off existing double GPO; new cable runs inside the wall cavity behind the tiles to the right-hand wall and through to the bathroom side.



Photo 2 – Bathroom: New double WGPO next to mirror, 400 mm above vanity top, cable entering from the left side.

Note: All new cabling will be hidden inside the wall cavity – no exposed cable or conduit on the kitchen or bathroom walls. Only the new WGPO will be visible. Red dashed lines on the photos show the approximate cable route inside the wall.

We sincerely appreciate the opportunity and look forward to doing business with you.