HTB ELECTRICAL & AIR CONDITIONING PTY LTD
ABN 54 168 092 466 | Licence 376869C

QUOTE

0403 116 368 | htbelectricalandaircon@outlook.com

BILL TO
[Client name]
[Street address]
[Suburb NSW Postcode]

CLIENT / SITE
[Client name]
[Street address]
[Suburb NSW Postcode]

QUOTE DETAILS
Quote No. 22
Date 2nd November 2026

DESCRIPTION	QTY	PRICE
- Supply 1 x 5kW Mitsubishi Electric split system air conditioner (reverse cycle, built-in Wi-Fi). + 1 x 5kW wall mounted indoor unit. + 1 x 5kW outdoor unit. - Supply all installation materials (copper pipes, cables, drain pipes, Colorbond trunking, anti-vibration rubber feet, brackets and electrical materials) and labour for air conditioning installation and electrical installation. + 1 x 5kW wall mounted indoor unit will be installed on the wall above the TV in the living room. A hole will be core drilled through the brick wall directly behind the indoor unit for the copper pipes, cables and drain pipe to go through to the balcony. + 1 x 5kW outdoor unit will be located on the floor of the balcony, right behind the TV wall, with anti-vibration rubber feet. The copper pipes, cables and drain pipe will be covered by Colorbond trunking along the outside wall down to the outdoor unit. The drain pipe will run to the floor waste of the balcony. + 1 x 20A circuit will be installed at the switchboard, with cable run to the isolation switch next to the outdoor unit on the balcony.	1	$3,330.00

SUBTOTAL	$3,330.00
GST	$333.00
TOTAL	**$3,663.00**

TERMS & CONDITIONS

Air Conditioning:

- Deposit: Upon acceptance of this quote, a 60% deposit is required to allow us to order the air conditioning unit and the materials required for the job.
- Final payment: The remaining 40% balance is payable upon completion of the work.
- Warranty: We provide a 5-year manufacturer's warranty on the air conditioning unit, together with a 1-year warranty on our installation workmanship, subject to the applicable warranty terms and conditions.
- Quote Validity: This quote is valid for 10 working days from the date of issue. After this period, pricing and availability may be subject to change.

Electrical:

- Payment is payable upon completion of the work.
- This quote will expire in 10 working days.

Method of payment:

Bank Transfer (EFT): **Name:** HTB ELECTRICAL & AIR CONDITIONING P/L
BSB: 082 343
Account Number: 84 378 4720

Or PayID to 0403 116 368